

DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER) BOARD AND CODE ADMINISTRATION DIVISION

MIAMI-DADE COUNTY PRODUCT CONTROL SECTION

11805 SW 26 Street, Room 208 Miami, Florida 33175-2474 T (786) 315-2590 F (786) 315-2599

www.miamidade.gov/pera

NOTICE OF ACCEPTANCE (NOA)

Carlisle SynTec, a division of Carlisle Construction Materials Inc. 1285 Ritner Highway Carlisle, PA 17013

SCOPE:

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER - Product Control Section to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein, and has been designed to comply with the Florida Building Code including the High Velocity Hurricane Zone of the Florida Building Code.

DESCRIPTION: Carlisle Sure-Weld Single Ply TPO Roof Systems over Steel Decks

LABELING: Each unit shall bear a permanent label with the manufacturer's name or logo, city, state and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

RENEWAL of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA

ADVERTISEMENT: The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This renews NOA# 13-0219.10 and consists of pages 1 through 24. The submitted documentation was reviewed by Alex Tigera.

(MIAMI-DADE COUNTY)
APPROVED

NOA No.: 14-0626.02 Expiration Date: 08/31/18 Approval Date: 08/28/14

Page 1 of 24

Stappet 7/0/15

ROOFING SYSTEM APPROVAL

Roofing **Category: Sub-Category:** Single Ply TPO Material: **Deck Type:** Steel Maximum Design Pressure Fire Classification: -90 psf

See General Limitation #1

TRADE NAMES OF PRODUCTS MANUFACTURED OR LABELED BY APPLICANT: TABLE 1

| Product Name | Dimensions | Test Specifications | Product Description |
|---|----------------------------|------------------------|---|
| Sure-Weld FleeceBACK | various | Specifications TAS 131 | Reinforced white or colored TPO |
| Suite 11 (1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 | , 41 10 6 10 | 1110 101 | membrane with fleece backing. |
| Sure-Weld AFX | various | TAS 131 | Reinforced white or colored TPO membrane with fleece backing. |
| Sure-Weld | various | TAS 131 | Reinforced white or colored TPO membrane. |
| Sure-Weld EXTRA | various | TAS 131 | Reinforced white or colored TPO membrane. |
| Sure-Weld HS | various | TAS 131 | Reinforced white or colored FR TPO membrane. |
| Sure-Weld Pressure Sensitive RUSS | various | TAS 131 | Reinforced Securement Strip. |
| Carlisle FAST 100 Adhesive | Various | TAS 131 | Polyurethane Adhesive |
| Carlisle Olybond 500BA | Various | TAS 110 | Polyurethane Adhesive |
| Carlisle One-Step Adhesive | Various | TAS 110 | Polyurethane Adhesive |
| Sure-Weld Bonding Adhesive | various | TAS 110 | Solvent-based bonding adhesive. |
| Aqua Base 120 Bonding Adhesive | Various | TAS 110 | Water-based bonding adhesive |
| Cold Applied Adhesive | Various | TAS 110 | Asphalt-Modified Polyether Adhesive |



NOA No.: 14-0626.02 **Expiration Date: 08/31/18** Approval Date: 08/28/14 Page 2 of 24

APPROVED INSULATIONS:

TABLE 2

| Product Name | Product Description | <u>Manufacturer</u> (With Current NOA) |
|------------------------------|---|---|
| Polyisocyanurate HP, HP-H | Polyisocyanurate roof insulation. | Carlisle Syntec, Inc. |
| Dens Deck, Dens Deck Prime | Silicon treated gypsum | Georgia-Pacific, Gypsum, LLC. |
| Wood Fiberboard | Regular Wood Fiber insulation board. | Generic |
| High Density Wood Fiberboard | High Density Wood Fiber insulation board. | Generic |
| Type X Gypsum | Gypsum Wallboard | Generic |
| XPS | Extruded polystyrene | Generic |
| EPS | Expanded polystyrene | Generic |

APPROVED FASTENERS:

TABLE 3

| <u>Fastener</u> <u>Number</u> | <u>Product</u> <u>Name</u> | <u>Product</u> <u>Description</u> | Dimensions | <u>Manufacturer</u> (With Current NOA) |
|----------------------------------|---|--|-------------------|---|
| 1. | HP Fastener, HPX Fastener, HP-XTRA Fastener | Insulation and membrane fastener | Various | Carlisle Syntec, Inc. |
| 2. | Insulation Fastening Plate | Metal plates used for insulation securement with Sure-Seal HP fasteners. | 3" dia | Carlisle Syntec, Inc. |
| 3. | Piranha, Piranha Xtra Plates | Metal plates used for membrane securement with HP-X & HP-Xtra fasteners. | 2-3/8" dia | Carlisle Syntec, Inc. |
| 4. | #12 Standard Roofgrip, #14 Roofgrip | Insulation and membrane fastener | Various | OMG, Inc. |
| 5. | #12 Standard Stainless Steel | Stainless steel insulation and membrane fastener | Various | OMG, Inc. |
| 6. | Trufast #14 HD Fasteners | Insulation and membrane fastener | Various | Altenloh, Brinck & Co. U.S., Inc. |
| 7. | Trufast #15 EHD Fasteners | Insulation and membrane fastener | Various | Altenloh, Brinck & Co. U.S., Inc. |
| 8. | Trufast #12 DP Fasteners | Insulation and membrane fastener | Various | Altenloh, Brinck & Co. U.S., Inc. |
| 9. | Trufast 3" Metal Insulation Plate | Insulation and membrane fastener | Various | Altenloh, Brinck & Co. U.S., Inc. |
| 10. | Trufast 2.4" Barbed Metal Seam Plate (14 Barb) | Insulation and membrane fastener | Various | Altenloh, Brinck & Co. U.S., Inc. |



NOA No.: 14-0626.02 Expiration Date: 08/31/18 Approval Date: 08/28/14 Page 3 of 24

EVIDENCE SUBMITTED:

| Test Agency | Test Identifier | Description | Date |
|--|------------------------|--|-------------|
| Architectural Testing Inc. | ATI-37050.01 | Wind Uplift Classification | 3/13/00 |
| The state of the s | ATI-37490.01 | ASTM D 2137 | 7/7/00 |
| | | | |
| Factory Mutual Research Corp. | 3003393 | Class 4470 | 3/30/99 |
| | 3003393 | Wind Uplift Classification | 3/26/99 |
| | (Letter Report) | | |
| | 3001522 | Wind Uplift Classification | 3/26/99 |
| | 3001522 | Wind Uplift Classification | 11/3/98 |
| | (Letter Report) | | |
| | 3Z9A1.AM | Wind Uplift Classification | 10/15/97 |
| | Approval Guide Excerpt | Wind Uplift Classification Listings | 5/00 |
| | 3B8Q4.AM | S | 06/04/97 |
| | 3006664 | | 08/08/00 |
| | 1B7A5.AM | | 02/23/98 |
| | 3026316 | | 04/24/07 |
| | 3011494 | | |
| | 3007710 | | 03/12/01 |
| | 3011329 | | 06/10/02 |
| | 3013584 | Class 4470 | 06/27/03 |
| | 3011220 | Class 4470 | 08/16/01 |
| | 3006110 | Class 4470 | 06/13/01 |
| | 3012879 | Class 4470 | 04/04/03 |
| | 3017662 | Class 4470 | 06/07/05 |
| | 3013584 | Class 4470 | 06/27/03 |
| | 3020845 | Class 4470 | 01/25/06 |
| | 3019897 | Class 4470 | 10/07/05 |
| | 3022187 | Class 4470 | 09/15/05 |
| | 3022181 | Class 4470 | 09/01/05 |
| | 3023032 | Class 4470 | 07/20/05 |
| Celotex Corporation Testing Services | 520257 | Membrane Physical Property Testing | 4/19/00 |
| SGS U.S Testing Company Incorporated | 131248-R2 | Ozone Resistance | 1/6/00 |
| Trinity ERD | C46470.07.14-1A | TAS 131 | 07/16/14 |
| | C46470.07.14-1B | TAS 131 | 07/16/14 |
| | C46470.07.14-2A | TAS 131 | 07/30/14 |
| | C46470.07.14-4-R1 | TAS 131 | 07/21/14 |



NOA No.: 14-0626.02 Expiration Date: 08/31/18 Approval Date: 08/28/14 Page 4 of 24

APPROVED ASSEMBLIES

Membrane Type: Single Ply, Thermoplastic, TPO, Reinforced, FleeceBACK

Deck Type 21: Steel, Insulated **Deck Description:** 18-22 ga. Steel

System Type A(1): All layers of insulation adhered to deck, membrane fully adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

| Insulation Layer | Insulation Fasteners (Table 3) | <u>Fastener</u> <u>Density/ft²</u> |
|--|-----------------------------------|---------------------------------------|
| Polyisocyanurate HP-H, XPS, EPS | | |
| Minimum 1" thick | N/A | N/A |
| Dens Deck, Dens Deck Prime | | |
| Minimum ¼" thick | N/A | N/A |
| High Density Wood Fiberboard, Wood Fiber | | |
| Minimum ½" thick | N/A | N/A |

Note: All insulation shall be fully adhered to the deck with Carlisle FAST 100 Adhesive at a rate of 1 gal./sq. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Vapor Retarder: None.

Barrier: None.

Membrane #1: Sure-Weld, Sure-Weld HS, Reinforced, 45 or 60 mil membrane or Sure-Weld EXTRA 80 mil

membrane fully adhered to the insulation using Sure-Weld Bonding Adhesive applied to the substrate at a rate of 1 gal/60 ft.² (finished surface) or Aqua Base 120 Bonding Adhesive applied to the substrate at a rate of 1 gal/60 ft.² (finished surface). Outside 1.5" of side laps are heat

welded.

Membrane #2: Sure-Weld FleeceBACK 100 or 115 mil membrane fully adhered to the insulation using Carlisle

FAST 100 Adhesive applied to the substrate at a rate of 1 gal/sq or Aqua Base 120 Bonding Adhesive applied to the substrate at a rate of 1 gal/120 ft.² Outside 1.5" of side laps are heat

welded.

Membrane #3: Sure-Weld AFX membrane adhered to the insulation in a full mopping of approved asphalt

applied within the EVT range and at a rate of 20-25 lbs./sq. or Cold Applied Adhesive applied to

the substrate at a rate of 1 gal/67 ft.² Outside 1.5" of side laps are heat welded.

Maximum Design

Pressure:

-60 psf. (See General Limitation #9)



NOA No.: 14-0626.02 Expiration Date: 08/31/18 Approval Date: 08/28/14 Page 5 of 24

Deck Type 2I: Steel, Insulated **Deck Description:** 18-22 ga. Steel

System Type C(1): All layers of insulation simultaneously attached; membrane fully adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

| Base Insulation Layer | Insulation Fasteners | <u>Fastener</u> |
|--|---------------------------------------|--|
| | <u>(Table 3)</u> | Density/ft ² |
| The following covered with the boards listed in "Base or Top Ins XPS, EPS | ulation Layer". | |
| Minimum 1" thick | N/A | N/A |
| Base or Top Insulation Layer | Insulation Fasteners (Table 3) | <u>Fastener</u> Density/ft ² |
| Polyisocyanurate HP, Polyisocyanurate HP-H, | | |
| Minimum 1.4" thick | 1, 2, 4, 5 | 1:3.2 ft ² |
| Minimum 2" thick | 1, 2, 6, 7, 8, 9 | 1:4 ft ² |
| Dens Deck, Dens Deck Prime | | |
| Minimum 1/4" thick | 1, 2, 6, 7, 8, 9 | 1:2 ft ² |

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Single and multiple layers of insulation can be attached to base layer with Carlisle FAST 100 Adhesive, Carlisle OlyBond 500BA, or Carlisle One-Step Adhesive.

Note: Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Vapor Retarder: (Optional) Any UL or FMRC approved vapor retarder applied to the roof deck or over a base

layer of insulation.

Barrier: None.

Membrane #1: Sure-Weld, Sure-Weld HS, Reinforced, 45 or 60 mil membrane or Sure-Weld EXTRA 80 mil

membrane fully adhered to the insulation using Sure-Weld Bonding Adhesive applied to the substrate at a rate of 1 gal/60 ft.² (finished surface). Outside 1.5" of side laps are heat welded.

Maximum Design Pressure -45 psf (See General Limitation #9)



NOA No.: 14-0626.02 Expiration Date: 08/31/18 Approval Date: 08/28/14 Page 6 of 24

Membrane #2:

Sure-Weld FleeceBACK 100 or 115 mil membrane fully adhered to the insulation using Aqua Base 120 Bonding Adhesive applied to the substrate at a rate of 1 gal/120 ft.² Outside 1.5" of side laps are heat welded.

Maximum Design Pressure -45 psf. (See General Limitation #9)

Sure-Weld FleeceBACK 100 or 115 mil membrane fully adhered to the insulation using Carlisle FAST 100 Adhesive applied to the substrate at a rate of 1 gal/sq. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure -60 psf. (See General Limitation #9)

Maximum Design Pressure:

See Membrane Options Above



NOA No.: 14-0626.02 Expiration Date: 08/31/18 Approval Date: 08/28/14

Page 7 of 24

Deck Type 2I: Steel, Insulated

Deck Description: Minimum 22 gage, Type B, ASTM A 653 SS Grade 33 Steel deck fastened to steel support at a

maximum span of 6 feet o.c. Steel deck shall be fastened with minimum ITW Buildex Traxx/4 at a maximum spacing of 6 inches o.c. Side laps shall be fastened with ITW Buildex Traxx/1 at a

maximum spacing of 24 inches o.c.

System Type C(2): All layers of insulation simultaneously attached; membrane fully adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

| Base Insulation Layer | Insulation Fasteners (Table 3) | <u>Fastener</u> <u>Density/ft²</u> |
|---|--------------------------------|---------------------------------------|
| One of the following covered with the boards listed in Top Layer XPS, EPS | or Base or Top Layer. | |
| Minimum 1" thick | N/A | N/A |
| Polyisocyanurate HP, Polyisocyanurate HP-H | | |
| Minimum 1.5" thick | N/A | N/A |
| High Density Wood Fiberboard | | |
| Minimum 3/4" thick | N/A | N/A |
| Wood Fiber | | |
| Minimum 1" thick | N/A | N/A |
| Dens Deck, Dens Deck Prime | | |
| Minimum 1/4" thick | N/A | N/A |

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Single and multiple layers of insulation can be attached to base layer with Carlisle FAST 100 Adhesive, Carlisle OlyBond 500BA, or Carlisle One-Step Adhesive.

| Top Insulation Layer | Insulation Fasteners (Table 3) | <u>Fastener</u> <u>Density/ft²</u> |
|--|--------------------------------|---------------------------------------|
| Required over the insulations listed in Base Insulation Layer: | | |
| Plywood | | |
| Minimum 19/32" thick | 1, 2 | 1:1.9 ft ² |

Note: Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Vapor Retarder: (Optional) Any UL or FMRC approved vapor retarder applied to the roof deck or over a base layer of insulation.



NOA No.: 14-0626.02 Expiration Date: 08/31/18 Approval Date: 08/28/14

Page 8 of 24

Barrier: None.

Membrane #1: Sure-Weld, Sure-Weld HS, Reinforced, 45 or 60 mil membrane or Sure-Weld EXTRA 80 mil

membrane fully adhered to the insulation using Sure-Weld Bonding Adhesive applied to the substrate at a rate of 1 gal/60 ft.² (finished surface). Outside 1.5" of side laps are heat welded.

Maximum Design Pressure –75 psf (See General Limitation #7)

Or

Sure-Weld, Sure-Weld HS, Reinforced, 45 or 60 mil membrane or Sure-Weld EXTRA, 80 mil membrane fully adhered to the insulation using Aqua Base 120 Bonding Adhesive applied to the substrate at a rate of 1 gal/120 ft.² (finished surface). Outside 1.5" of side laps are heat welded.

Maximum Design Pressure -52.5 psf (See General Limitation #7)

Membrane #2: Sure-Weld FleeceBACK 100 or 115 mil membrane fully adhered to the insulation using Carlisle

FAST 100 Adhesive applied to the substrate at a rate of 1 gal/sq. Outside 1.5" of side laps are

heat welded.

Maximum Design Pressure –75 psf. (See General Limitation #7)

Or

Sure-Weld FleeceBACK 100 or 115 mil membrane fully adhered to the insulation using Aqua Base 120 Bonding Adhesive applied to the substrate at a rate of 1 gal/120 ft.² Outside 1.5" of

side laps are heat welded.

Maximum Design Pressure -67.5 psf. (See General Limitation #7)

Maximum Design Pressure:

See Membrane Options Above



NOA No.: 14-0626.02 Expiration Date: 08/31/18 Approval Date: 08/28/14 Page 9 of 24

Deck Type 2I: Steel, Insulated

Deck Description: Minimum 22 gage (min 0.0294in.) ASTM A 653 SS Grade 33 Steel deck fastened to steel

support at a maximum span of 6 feet o.c. Steel deck shall be fastened with minimum ITW Buildex Traxx/4 at a maximum spacing of 6 inches o.c. Side laps shall be fastened with ITW

Buildex Traxx/1 at a maximum spacing of 24 inches o.c.

System Type C(3): All layers of insulation simultaneously attached; membrane fully adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

| Insulation Layer | Insulation Fasteners | Fastener |
|--|-----------------------------|-------------------------|
| | <u>(Table 3)</u> | Density/ft ² |
| Polyisocyanurate HP, Polyisocyanurate HP-H | | |
| Minimum 2" thick | 1, 2, 6, 7, 8, 9 | 1:1.6 ft ² |

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Single and multiple layers of insulation can be attached to base layer with Carlisle FAST 100 Adhesive.

Note: Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Vapor Retarder: (Optional) Any UL or FMRC approved vapor retarder applied to the roof deck or over a base

layer of insulation.

Barrier: None.

Membrane #1: Sure-Weld, Sure-Weld HS, Reinforced, 45 or 60 mil membrane or Sure-Weld EXTRA 80 mil

membrane fully adhered to the insulation using Sure-Weld Bonding Adhesive applied to the substrate at a rate of 1 gal/60 ft.² (finished surface). Outside 1.5" of side laps are heat welded.

Maximum Design Pressure -75 psf (See General Limitation #7)

Membrane #2: Sure-Weld FleeceBACK 100 or 115 mil membrane fully adhered to the insulation using Carlisle

FAST 100 Adhesive applied to the substrate at a rate of 1 gal/sq. Outside 1.5" of side laps are

heat welded.

Maximum Design Pressure –75 psf. (See General Limitation #7)

Membrane #3: Sure-Weld AFX membrane adhered to the insulation using Cold Applied Adhesive applied to the

substrate at a rate of 1 gal/67 ft.² Outside 1.5" of side laps are heat welded.

Maximum Design Pressure -60 psf. (See General Limitation #7)

Maximum Design

Pressure:

See Membrane Options Above



NOA No.: 14-0626.02 Expiration Date: 08/31/18 Approval Date: 08/28/14 Page 10 of 24

Deck Type 2I: Steel, Insulated

Deck Description: Minimum 22 gage ASTM A 611 Grade E or A653 Grade 80 Steel deck fastened to steel support

at a maximum span of 6 feet o.c. Steel deck shall be fastened with minimum ITW Buildex Traxx/5 at a maximum spacing of 6 inches o.c. Side laps shall be fastened with ITW Buildex

Traxx/1 at a maximum spacing of 24 inches o.c.

System Type C(4): All layers of insulation simultaneously attached; membrane fully adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

| Base Insulation Layer | <u>Insulation Fasteners</u> (<u>Table 3</u>) | <u>Fastener</u> <u>Density/ft²</u> |
|---|---|---------------------------------------|
| One of the following covered with the boards listed in Top Layer. | | |
| XPS, EPS | | |
| Minimum 1" thick | N/A | N/A |
| Polyisocyanurate HP, Polyisocyanurate HP-H | | |
| Minimum 1.5" thick | N/A | N/A |
| High Density Wood Fiberboard | | |
| Minimum ¾" thick | N/A | N/A |
| Wood Fiber | | |
| Minimum 1" thick | N/A | N/A |

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment. Single and multiple layers of insulation can be attached to base layer with Carlisle FAST 100 Adhesive.

| Top Insulation Layer | <u>Insulation Fasteners</u> (<u>Table 3</u>) | <u>Fastener</u> <u>Density/ft²</u> |
|---|---|---------------------------------------|
| Required over the insulations listed in Base Layer. | | |
| Dens Deck Prime (For use over all insulation types.) Minimum 5/8" thick | 5 | 1:1.33 ft² |
| William /8 thick | 3 | 1.1.33 11 |

Note: Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Vapor Retarder: (Optional) Any UL or FMRC approved vapor retarder applied to the roof deck or over a base

layer of insulation.



NOA No.: 14-0626.02 Expiration Date: 08/31/18 Approval Date: 08/28/14 Page 11 of 24 Barrier: None.

Membrane: Sure-Weld or Sure-Weld HS Reinforced, 45 or 60 mil membrane or Sure-Weld EXTRA 80 mil

membrane fully adhered to the insulation using Sure-Weld Bonding Adhesive applied to the substrate at a rate of 1 gal/60 ft.². (finished surface). Outside 1.5" of side laps are heat welded.

Maximum Design Pressure:

-90 psf (See General Limitation #7)



NOA No.: 14-0626.02 Expiration Date: 08/31/18 Approval Date: 08/28/14 Page 12 of 24

Deck Type 2I: Steel, Insulated

Deck Description: Minimum 22 gage (min 0.0295in.) Type B, ASTM A 611 Grade E or ASTM A 653 Grade 80

Steel deck fastened to steel support at a maximum span of 6 feet o.c. Steel deck shall be fastened with minimum ITW Buildex Traxx/4 at a maximum spacing of 6 inches o.c. Side laps shall be

fastened with ITW Buildex Traxx/1 at a maximum spacing of 30 inches o.c.

System Type D(1): Membrane mechanically attached over preliminarily fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

| Base Insulation Layer | Insulation Fasteners | Fastener |
|--|-----------------------------|-------------------------|
| | <u>(Table 3)</u> | Density/ft ² |
| One of the following covered with the boards listed in "Base or To | op Insulation Layer". | |
| XPS, EPS | | |
| Minimum 1" thick | N/A | N/A |
| | | _ |
| Base or Top Insulation Layer | <u>Insulation Fasteners</u> | <u>Fastener</u> |
| | <u>(Table 3)</u> | Density/ft ² |
| Polyisocyanurate HP, Polyisocyanurate HP-H | | |
| Minimum 1.2" thick | N/A | N/A |
| | | |
| Wood Fiber | | |
| Minimum ½" thick | N/A | N/A |
| High Density Wood Fiberboard | | |
| Minimum ¾" thick | N/A | N/A |
| William /4 thick | 1V/ A | IV/A |
| Dens Deck, Dens Deck Prime | | |
| Minimum 1/4" thick | N/A | N/A |
| | | |

Note: All layers of insulation and base sheet shall be simultaneously attached. See base sheet below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane. At an application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft. Single and multiple layers of insulation can be attached to the deck with Carlisle FAST 100 Adhesive, Carlisle Olybond 500BA, Carlisle One-Step Adhesive.

Vapor Retarder: (Optional) Any UL or FMRC approved vapor retarder applied to the roof deck or over a base

layer of insulation.

Barrier: None.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA, Reinforced, secured through the preliminarily

attached insulation as specified below.



NOA No.: 14-0626.02 Expiration Date: 08/31/18 Approval Date: 08/28/14 Page 13 of 24 Fastening #1: HPX Fasteners with Piranha Plates 6" o.c. through the Sure-Weld or Sure-Weld EXTRA

Membrane in the lap in rows spaced 7'-6" o.c. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure -67.5 psf. (See General Limitation #7)

Fastening #2: HPX Fasteners with Piranha Plates 6" o.c. through the Sure-Weld or Sure-Weld EXTRA

Membrane in the lap or through a Sure-Weld Pressure-Sensitive RUSS Strip in rows spaced 9'-7"

o.c. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure -60 psf. (See General Limitation #7)

Fastening #3: HPX Fasteners with Piranha Plates 6" o.c. through the Sure-Weld HS Membrane in the lap or

through a Sure-Weld Pressure-Sensitive RUSS Strip in rows spaced 9'-6" o.c. Outside 1.5" of

side laps are heat welded.

Maximum Design Pressure -52.5 psf. (See General Limitation #7)

Fastening #4: HP-XTRA Fasteners with Piranha Xtra Plates 12" o.c. through the Sure-Weld or Sure-Weld

EXTRA Membrane in the lap or through a Sure-Weld Pressure-Sensitive RUSS Strip in rows spaced 9'-7" o.c. Outside 1.5" of side laps are heat welded. Outside 1.5" of side laps are heat

welded.

Maximum Design Pressure -45 psf. (See General Limitation #7)

Fastening #5: HPX Fasteners with Piranha Plates 12" o.c. through the Sure-Weld or Sure-Weld EXTRA

Membrane in the lap or through a Sure-Weld Pressure-Sensitive RUSS Strip in rows spaced 7'-

7" o.c. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure -45 psf. (See General Limitation #7)

Maximum Design

Pressure:

See Fastening Options Above



NOA No.: 14-0626.02 Expiration Date: 08/31/18 Approval Date: 08/28/14 Page 14 of 24

Deck Type 2I: Steel, Insulated

Deck Description: Minimum 22 gage Type B, ASTM A 1008SS Grade 80 or ASTM A 653 Grade 80 Steel deck

fastened to steel support at a maximum span of 6 feet o.c. Steel deck shall be fastened with minimum ITW Buildex Traxx/4 at a maximum spacing of 6 inches o.c. Side laps shall be

fastened with ITW Buildex Traxx/1 at a maximum spacing of 30 inches o.c.

System Type D(2): Membrane mechanically attached over preliminarily fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

| Base Insulation Layer | Insulation Fasteners (Table 3) | <u>Fastener</u> <u>Density/ft²</u> | |
|---|-----------------------------------|---------------------------------------|--|
| One of the following covered with the boards listed in "Base or Top Insulation" Layer. XPS, EPS | | | |
| Minimum 1" thick | N/A | N/A | |
| Base or Top Insulation Layer | Insulation Fasteners (Table 3) | <u>Fastener</u> <u>Density/ft²</u> | |
| Polyisocyanurate HP, Polyisocyanurate HP-H Minimum 1.2" thick | N/A | N/A | |
| Wood Fiber Minimum ½" thick | N/A | N/A | |
| High Density Wood Fiberboard Minimum ¾" thick | N/A | N/A | |
| Dens Deck, Dens Deck Prime Minimum ¼" thick | N/A | N/A | |

Note: All layers of insulation and base sheet shall be simultaneously attached. See base sheet below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane. At an application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft. Single and multiple layers of insulation can be attached to the deck with Carlisle FAST 100 Adhesive, Carlisle Olybond 500BA, Carlisle One-Step Adhesive.

Vapor Retarder: (Optional) Any UL or FMRC approved vapor retarder applied to the roof deck or over a base

layer of insulation.

Barrier: None.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA, Reinforced, secured through the preliminarily

attached insulation as specified below.



NOA No.: 14-0626.02 Expiration Date: 08/31/18 Approval Date: 08/28/14 Page 15 of 24

HPX Fasteners with Piranha Plates 6" o.c. through the Sure-Weld HS Membrane in the lap or Fastening #1:

through a Sure-Weld Pressure-Sensitive RUSS Strip in rows spaced 7'-7" o.c. Outside 1.5" of

side laps are heat welded.

Maximum Design Pressure -60 psf. (See General Limitation #7)

HPX Fasteners with Piranha Plates 6" o.c. through the Sure-Weld or Sure-Weld EXTRA **Fastening #2:**

Membrane in the lap or through a Sure-Weld Pressure-Sensitive RUSS Strip in rows spaced 11'-

6.5" o.c. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure -60 psf. (See General Limitation #7)

Maximum Design

Pressure:

See Fastening Options Above



NOA No.: 14-0626.02 **Expiration Date: 08/31/18** Approval Date: 08/28/14

Page 16 of 24

Deck Type 2I: Steel, Insulated

Deck Description: Minimum 22 gage Type B, ASTM A 653 Grade 33 Steel deck fastened to steel support at a

maximum span of 6 feet o.c. Steel deck shall be fastened with minimum ITW Buildex Traxx/4 at a maximum spacing of 6 inches o.c. Side laps shall be fastened with ITW Buildex Traxx/1 at a

maximum spacing of 30 inches o.c.

System Type D(3): Membrane mechanically attached over preliminarily fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

| Base Insulation Layer | Insulation Fasteners (Table 3) | <u>Fastener</u> <u>Density/ft²</u> | |
|---|-----------------------------------|---------------------------------------|--|
| One of the following covered with the boards listed in "Base or Top Insulation Layer". XPS, EPS | | | |
| Minimum 1" thick | N/A | N/A | |
| Base or Top Insulation Layer | Insulation Fasteners (Table 3) | <u>Fastener</u> <u>Density/ft²</u> | |
| Polyisocyanurate HP, Polyisocyanurate HP-H Minimum 1.2" thick | N/A | N/A | |
| Wood Fiber Minimum ½" thick | N/A | N/A | |
| High Density Wood Fiberboard Minimum ¾" thick | N/A | N/A | |
| Dens Deck, Dens Deck Prime Minimum ¼" thick | N/A | N/A | |

Note: All layers of insulation and base sheet shall be simultaneously attached. See base sheet below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane. At an application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft. Single and multiple layers of insulation can be attached to the deck with Carlisle FAST 100 Adhesive, Carlisle Olybond 500BA, Carlisle One-Step Adhesive.

Vapor Retarder: (Optional) Any UL or FMRC approved vapor retarder applied to the roof deck or over a base

layer of insulation.

Barrier: None.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA, Reinforced, secured through the preliminarily

attached insulation as specified below.



NOA No.: 14-0626.02 Expiration Date: 08/31/18 Approval Date: 08/28/14 Page 17 of 24 Fastening #1: HPX Fasteners with Piranha Plates 6" o.c. through the Sure-Weld or Sure-Weld EXTRA

Membrane in the lap or through a Sure-Weld Pressure-Sensitive RUSS Strip in rows spaced 11'-

6.5" o.c. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure –52.5 psf. (See General Limitation #7)

Fastening #2: HP-XTRA Fasteners with Piranha Xtra Plates 6" o.c. through the Sure-Weld or Sure-Weld

EXTRA Membrane in the lap or through a Sure-Weld Pressure-Sensitive RUSS Strip in rows

spaced 11'-6.5" o.c. Outside 1.5" of side laps are heat welded *Maximum Design Pressure –60 psf. (See General Limitation #7)*

Maximum Design

Pressure:

See Fastening Options Above



NOA No.: 14-0626.02 Expiration Date: 08/31/18 Approval Date: 08/28/14

Page 18 of 24

Deck Type 2I: Steel, Insulated

Deck Description: Minimum 22 gage (min 0.0295in.) Type B, Grade E Steel deck fastened to steel support at a

maximum span of 6 feet o.c. Steel deck shall be fastened with minimum ITW Buildex Traxx/4 at a maximum spacing of 6 inches o.c. Side laps shall be fastened with ITW Buildex Traxx/1 at a

maximum spacing of 24 inches o.c.

System Type D(4): Membrane mechanically attached over preliminarily fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

| Base Insulation Layer | Insulation Fasteners (Table 3) | Fastener Density/ft ² |
|---|-----------------------------------|---------------------------------------|
| One of the following covered with the boards listed in "Base or To XPS, EPS | pp Insulation Layer". | |
| Minimum 1" thick | N/A | N/A |
| Base or Top Insulation Layer | Insulation Fasteners (Table 3) | <u>Fastener</u> <u>Density/ft²</u> |
| Polyisocyanurate HP, Polyisocyanurate HP-H Minimum 1.5" thick | N/A | N/A |
| Wood Fiber Minimum ½" thick | N/A | N/A |
| High Density Wood Fiberboard Minimum ¾" thick | N/A | N/A |
| Dens Deck, Dens Deck Prime Minimum ¼" thick | N/A | N/A |

Note: All layers of insulation and base sheet shall be simultaneously attached. See base sheet below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane. At an application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft. Single and multiple layers of insulation can be attached to the deck with Carlisle FAST 100 Adhesive, Carlisle Olybond 500BA, Carlisle One-Step Adhesive.



NOA No.: 14-0626.02 Expiration Date: 08/31/18 Approval Date: 08/28/14 Page 19 of 24 **Vapor Retarder:** (Optional) Any UL or FMRC approved vapor retarder applied to the roof deck or over a base

layer of insulation.

Barrier: None.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA, Reinforced, secured through the preliminarily

attached insulation as specified below.

Fastening #1: HPX Fasteners with Piranha Plates 9" o.c. through the Sure-Weld or Sure-Weld EXTRA

Membrane in the lap or through a Sure-Weld Pressure-Sensitive RUSS Strip in rows spaced 9'-6"

o.c. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure -52.5 psf. (See General Limitation #7)

Fastening #2: HPX Fasteners with Piranha Plates 9" o.c. through the Sure-Weld HS Membrane in the lap or

through a Sure-Weld Pressure-Sensitive RUSS Strip in rows spaced 9'-7" o.c. Outside 1.5" of

side laps are heat welded.

Maximum Design Pressure -45 psf. (See General Limitation #7)

Maximum Design

See Fastening Options Above

Pressure:



NOA No.: 14-0626.02 Expiration Date: 08/31/18 Approval Date: 08/28/14 Page 20 of 24

Deck Type 2I: Steel, Insulated

Deck Description: Minimum 22 gage Type B, ASTM A 1008 SS Grade 33 Steel deck fastened to steel support at a

maximum span of 5 feet o.c. Steel deck shall be fastened with minimum ITW Buildex Traxx/4 at a maximum spacing of 6 inches o.c. Side laps shall be fastened with ITW Buildex Traxx/1 at a

maximum spacing of 24 inches o.c.

System Type D(5): Membrane mechanically attached over preliminarily fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

| Base Insulation Layer | Insulation Fasteners (Table 3) | Fastener Density/ft ² |
|---|-----------------------------------|---------------------------------------|
| One of the following covered with the boards listed in "Base or To XPS, EPS | p Insulation Layer". | |
| Minimum 1" thick | N/A | N/A |
| Base or Top Insulation Layer | Insulation Fasteners (Table 3) | <u>Fastener</u> <u>Density/ft²</u> |
| Polyisocyanurate HP, Polyisocyanurate HP-H | | |
| Minimum 1.2" thick | N/A | N/A |
| Wood Fiber | | |
| Minimum ½" thick | N/A | N/A |
| High Density Wood Fiberboard | | |
| Minimum ¾" thick | N/A | N/A |
| Dens Deck, Dens Deck Prime | | |
| Minimum ¹ / ₄ " thick | N/A | N/A |

Note: All layers of insulation and base sheet shall be simultaneously attached. See base sheet below for fasteners and density. Refer to Roofing Application Standard RAS 117 for insulation attachment requirements. Insulation shall have preliminary attachment, prior to the installation of the roofing membrane. At an application rate of two fasteners per board for insulation boards having no dimension greater than 4 ft., and four fasteners for any insulation board having no dimension greater than 8 ft. Single and multiple layers of insulation can be attached to the deck with Carlisle FAST 100 Adhesive, Carlisle Olybond 500BA, Carlisle One-Step Adhesive.

Vapor Retarder: (Optional) Any UL or FMRC approved vapor retarder applied to the roof deck or over a base

layer of insulation.

Barrier: None.

Membrane: Sure-Weld, Sure-Weld HS or Sure-Weld EXTRA, Reinforced, secured through the preliminarily

attached insulation as specified below.



NOA No.: 14-0626.02 Expiration Date: 08/31/18 Approval Date: 08/28/14 Page 21 of 24 Fastening #11: HPX Fasteners with Piranha Plates 6" o.c. through the Sure-Weld or Sure-Weld EXTRA

Membrane in the lap in rows spaced 3'-6" o.c. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure –82.5 psf. (See General Limitation #7)

Fastening #12: HPX Fasteners with Piranha Plates 12" o.c. through the Sure-Weld or Sure-Weld EXTRA

Membrane in the lap or through a Sure-Weld Pressure-Sensitive RUSS Strip in rows spaced 3'-6"

o.c. Outside 1.5" of side laps are heat welded.

Maximum Design Pressure –52.5 psf. (See General Limitation #7)

Maximum Design

Pressure:

See Fastening Options Above



NOA No.: 14-0626.02 Expiration Date: 08/31/18 Approval Date: 08/28/14

Page 22 of 24

STEEL DECK SYSTEM LIMITATIONS:

- If mechanical attachment to the structural deck through the lightweight insulating concrete is proposed, a field withdrawal resistance testing shall be performed to determine equivalent or enhanced fastener patterns and density. All testing and fastening design shall be in compliance with Testing Application Standard TAS 105 and Roofing Application Standard RAS 137, calculations shall be signed and sealed by a Florida registered Professional Engineer, Registered Architect, or Registered Roof Consultant.
- 2. For steel deck application where specific deck construction is not referenced: The deck shall be a minimum 22 gage attached with 5/8" puddle welds with weld washers at every flute with maximum deck spans of 5 ft. o.c.



NOA No.: 14-0626.02 Expiration Date: 08/31/18 Approval Date: 08/28/14 Page 23 of 24

GENERAL LIMITATIONS:

- 1. Fire classification is not part of this acceptance, refer to a current Approved Roofing Materials Directory for fire ratings of this product.
- 2. Insulation may be installed in multiple layers. The first layer shall be attached in compliance with Product Control Approval guidelines. All other layers shall be adhered in a full mopping of approved asphalt applied within the EVT range and at a rate of 20-40 lbs./sq., or mechanically attached using the fastening pattern of the top layer
- 3. All standard panel sizes are acceptable for mechanical attachment. When applied in approved asphalt, panel size shall be 4' x 4' maximum.
- 4. An overlay and/or recovery board insulation panel is required on all applications over closed cell foam insulations when the base sheet is fully mopped. If no recovery board is used the base sheet shall be applied using spot mopping with approved asphalt, 12" diameter circles, 24" o.c.; or strip mopped 8" ribbons in three rows, one at each sidelap and one down the center of the sheet allowing a continuous area of ventilation. Encircling of the strips is not acceptable. A 6" break shall be placed every 12' in each ribbon to allow cross ventilation. Asphalt application of either system shall be at a minimum rate of 12 lbs./sq. Note: Spot attached systems shall be limited to a maximum design pressure of -45 psf.
- 5. Fastener spacing for insulation attachment is based on a Minimum Characteristic Force (F') value of 275 lbf., as tested in compliance with Testing Application Standard TAS 105. If the fastener value, as field-tested, are below 275 lbf. insulation attachment shall not be acceptable.
- 6. Fastener spacing for mechanical attachment of anchor/base sheet or membrane attachment is based on a minimum fastener resistance value in conjunction with the maximum design value listed within a specific system. Should the fastener resistance be less than that required, as determined by the Building Official, a revised fastener spacing, prepared, signed and sealed by a Florida Registered Engineer, Architect, or Registered Roof Consultant may be submitted. Said revised fastener spacing shall utilize the withdrawal resistance value taken from Testing Application Standards TAS 105 and calculations in compliance with Roofing Application Standard RAS 117.
- 7. Perimeter and corner areas shall comply with the enhanced uplift pressure requirements of these areas. Fastener densities shall be increased for both insulation and base sheet as calculated in compliance with Roofing Application Standard RAS 117 and/or RAS 137. Calculations prepared, signed and sealed by a Florida registered Professional Engineer, Registered Architect, or Registered Roof Consultant (When this limitation is specifically referred within this NOA, General Limitation #9 will not be applicable.)
- 8. All attachment and sizing of perimeter nailers, metal profile, and/or flashing termination designs shall conform with Roofing Application Standard RAS 111 and applicable wind load requirements.
- 9. The maximum designed pressure limitation listed shall be applicable to all roof pressure zones (i.e. field, perimeters, and corners). Neither rational analysis, nor extrapolation shall be permitted for enhanced fastening at enhanced pressure zones (i.e. perimeters, extended corners and corners). (When this limitation is specifically referred within this NOA, General Limitation #7 will not be applicable.)
- All membranes or packaging shall bear the imprint or identifiable marking of the manufacturer's name or logo and the following statement: "Miami-Dade County Product Control Approved" or the Miami-Dade County Product Control Seal as shown below.



11. All products listed herein shall have a quality assurance audit in accordance with the Florida Building Code and Rule 61G20-3 of the Florida Administrative Code.

END OF THIS ACCEPTANCE



NOA No.: 14-0626.02 **Expiration Date: 08/31/18** Approval Date: 08/28/14

Page 24 of 24