

## DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER) BOARD AND CODE ADMINISTRATION DIVISION

#### NOTICE OF ACCEPTANCE (NOA)

MIAMI-DADE COUNTY PRODUCT CONTROL SECTION

11805 SW 26 Street, Room 208 Miami, Florida 33175-2474 T (786)315-2590 F (786) 315-2599

www.miamidade.gov/economy

GenFlex Roofing Systems A Division of Holcim Solutions and Products US, LLC 200 4<sup>th</sup> Ave. South Nashville, TN 37201

#### SCOPE:

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER - Product Control Section to be used in Miami-Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (in Miami-Dade County) and/or the AHJ (in areas other than Miami-Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein and has been designed to comply with the Florida Building Code including the High Velocity Hurricane Zone of the Florida Building Code.

#### **DESCRIPTION:** GenFlex EZ TPO Peel and Stick HW Single Ply Roof Systems over Steel Decks.

**LABELING:** Each unit shall bear a permanent label with the manufacturer's name or logo, city, state and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

**RENEWAL** of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

**TERMINATION** of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

**ADVERTISEMENT:** The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

**INSPECTION:** A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA renews and revises NOA No. 15-0428.20 and consists of pages 1 through 40.

The submitted documentation was reviewed by Jorge L. Acebo.

08/29/24

MIAMI-DADE COUNTY
APPROVED

NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 1 of 40

#### **ROOFING SYSTEM APPROVAL**

**Category:** Roofing

**Sub-Category:** Single Ply Roofing

Material: EZ TPO Peel and Stick HW

**Deck Type:** Steel **Maximum Design Pressure:** -90 psf.

# TRADE NAMES OF PRODUCTS MANUFACTURED OR LABELED BY APPLICANT: TABLE 1

		<u>Test</u>	
<b>Product</b>	<b>Dimensions</b>	<b>Specifications</b>	<b>Product Description</b>
EZ TPO Peel and Stick HW	Various	TAS 131	Reinforced TPO peel and stick membrane.
TPO Reinforced Curb Corner	Various	TAS 131	TPO curb flashing.
18" Curb Flashing	Various	TAS 131	TPO curb flashing.
TPO Inside/Outside Corner	Various	TAS 131	Molded TPO for corner flashing.
TPO Large Pipe Flashing	Various	TAS 131	TPO flashing for large round penetrations.
TPO T-Joint Cover	Various	TAS 131	TPO flashing for T-joints.
TPO Penetration Kit	Various	TAS 131	A penetration sealing kit for TPO.
TPO Walkway Pad	Various	TAS 131	TPO walkway pad.
TPO Coated Metal	Various	TAS 131	TPO laminated to hot-dipped galvanized steel for flashing.
TPO Premium Walkway Pad	Various	TAS 131	TPO walkway pad.
TPO Reinforced Split Pipe Boot	Various	TAS 131	TPO flashing for round penetrations 1" to 9" in diameter.
TPO 8" Reinforced Cover Strip	Various	TAS 131	8" wide 60 mil TPO cover strip.
TPO Universal Pipe Boot	Various	TAS 131	TPO flashing for round penetrations 1" to 6" in diameter.
TPO Unsupported Flashing	Various	TAS 131	Unreinforced TPO used for flashing.
V-Force	45" x 134"	Proprietary	A vapor retarder made of SBS modified bitumen adhesive laminated to a woven high density polyethylene top surface.
I.S.O. Stick	5 gal & 1500 ml	Proprietary	A dual component polyurethane adhesive.
I.S.O. Twin Pack Insulation Adhesive	1500 ml	Proprietary	A dual component polyurethane adhesive.
I.S.O. Spray R	15 gal pail & 55 gal drum	Proprietary	A two-part polyurethane adhesive.



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 2 of 40

## **APPROVED INSULATIONS:**

I ABLE 2			
Product Name	<b>Product Description</b>	Manufacturer (With Current NOA)	
DensDeck Prime	Silicon treated gypsum	Georgia Pacific Gypsum LLC	
SECUROCK Gypsum Fiber Roof Board	Rigid, gypsum-based board stock	USG Corp.	
GenFlex ISO Insulation GenFlex ISO Insulation Tapered	Polyisocyanurate foam insulation	Holcim Solutions and Products US, LLC	
GenFlex HD ISO	Polyisocyanurate with a coated fiberglass facer	Holcim Solutions and Products US, LLC	

## **APPROVED FASTENERS/ADHESIVES:**

Fastener Number	Product Name	TABLE 3 Product Description	Dimensions	Manufacturer (With Current NOA)
1.	Elevate Heavy-Duty	#15 Fastener for steel, Wood, concrete decks	N/A	Holcim Solutions and Products US, LLC
2.	Elevate All-Purpose Fastener	#14 Fastener for steel, Wood, concrete decks	N/A	Holcim Solutions and Products US, LLC
3.	Insulation Fastening Plate	Galvalume insulation plate	3" diameter	Holcim Solutions and Products US, LLC



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 3 of 40

## **EVIDENCE SUBMITTED:**

<b>Test Agency</b>	<b>Test Identifier</b>	<b>Description</b>	<u>Date</u>
UL LLC	R9516	UL 790	06/03/24
FM Approvals	3029384	4470	06/07/10
•	3033218	4470	08/12/08
	3033921	4470	01/12/09
	3039133	4470	04/07/11
	3035017	4470	08/22/12
	3038191	4470	08/04/11
	3035560	4470	01/11/10
	3047398	4470	08/15/13
	3042666	4470	08/14/12
	3041939	4470	08/14/12
	3030227	4470	06/18/07
	797-05604-267	4470	06/07/10
	797-07680-267	4470	09/12/12
	797-08513-267	4470	07/15/13
	797-05830-267	4470	08/30/10
	797-10191-267	4470	01/09/15
PRI Construction Materials	FBP-044-02-01, R10	TAS 114 H, J	06/01/17
Technologies, LLC	FBP-063-02-01	TAS 114 E	07/10/12
	FBP-085-02-01, Rev 1	TAS 114 J	10/04/12
	FBP-149-02-01	TAS 114 J	12/18/13
	FBP-154-02-02	FM 4474 D	12/18/13
	FBP-162-02-01	ASTM D 1970	05/15/14
	FBP-165-02-01	TAS 114 J	04/28/14
	FBP-166-02-01	ASTM D 6163	05/15/14
	FBP-175-02-01	TAS 114 J	04/28/14
	FBP-206-02-01	TAS 114 J	02/02/15
	FBP-208-02-01	TAS 131 ASTM D 6878	04/06/15
	FBP-222-02-03	TAS 114 C	04/01/15
	FBP-225-02-01	TAS 114 J	03/19/15
	FBP-233-02-03	TAS 114 J	06/01/15

## **DECK STRESS ANALYSIS CALCULATIONS/REPORTS**

Engineer/Agency	<b>Identifier</b>	<u>Assemblies</u>	<b>Date</b>
Zachary R. Priest, P.E.	Signed/Sealed	B(3), C(3), C(4), C(9), C(13), C(14), C(22)	10/03/16
	Calculations	B(2), B(4)	06/01/15
		C(10)	09/20/17
		C(11)	03/19/15
		C(16), C(18)	10/16/14
FM Approval Deck		B(5), B(6), B(7), C(1), C(12), C(15), C(19),	01/01/13
Limitations	N/A	C(20), C(21), C(23), C(247), C(25), C(26),	
Difficultions		C(27), C(28)	



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 4 of 40

#### APPROVED ASSEMBLIES

Membrane Type: Single Ply, TPO, Reinforced

**Deck Type 2I:** Steel Insulated

**Deck Description:** 18 - 22 ga. 33 ksi

System Type B(1): Base layer of insulation mechanically fastened, top layer adhered: membrane

self-adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft²
<b>GenFlex ISO Insulation</b>		
Minimum 1.5" thick	1 or 2 with 3	1:2 ft <sup>2</sup>
Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
<b>GenFlex ISO Insulation</b>	,	·
Minimum 1.5" thick	N/A	N/A
Tapered GenFlex ISO Insulation		
Minimum 1/2" thick with a 1/4" per ft. taper	N/A	N/A

Note: Base layer shall be mechanically attached with fasteners and density described. All other layers of insulation shall be adhered to base insulations with I.S.O. Twin Pack Insulation Adhesive applied in ½" to ¾" wide ribbons spaced 12" o.c. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

Membrane: Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld at

the 2" wide side laps.

**Maximum Design** 

**Pressure:** -45 psf. (See General Limitation #9)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 5 of 40

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga., Grade 33, Type B steel decking attached to steel supports

spaced 6 ft o.c. with 5/8" diameter puddle welds 6" o.c. and with side laps

attached using ½" – 14 HWH self-drilling fasteners spaced 24" o.c.

This Tested Assembly has been analyzed for allowable deck stress. See

**Evidence Submitted Table.** 

System Type B(2): Base layer of insulation mechanically fastened, top layer adhered: membrane

self-adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
GenFlex ISO Insulation	,	·
Minimum 2" thick	1 or 2 with 3	1:78 ft <sup>2</sup>
Middle Insulation Layer (Optional)	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
GenFlex ISO Insulation	,	v
Minimum ½" thick	N/A	N/A
Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
GenFlex HD ISO		-
Minimum ½" thick	N/A	N/A

Note: Base layer shall be mechanically attached with fasteners and density described. All other layers of insulation shall be adhered to base insulations with I.S.O. Twin Pack Insulation Adhesive in continuous ½" to ¾" wide beads spaced 6"o.c. or I.S.O. Spray R, or I.S.O. Stick applied in continuous ¾" to 1" wide ribbons spaced 6"o.c. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

Membrane: Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

**Maximum Design** 

**Pressure:** -60 psf. (See General Limitation #7)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 6 of 40

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga., Grade 33, Type B steel decking attached to steel supports

spaced 6 ft o.c. with 5/8" diameter puddle welds 6" o.c. and with side laps attached using  $\frac{1}{4}$ " –  $14 \times \frac{7}{8}$ " HWH self-drilling fasteners spaced 24" o.c.

This Tested Assembly has been analyzed for allowable deck stress. See

**Evidence Submitted Table.** 

System Type B(3): Base layer of insulation mechanically fastened, top layer adhered: membrane

self-adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer Insulation Fasteners Fastener (Table 3) Density/ft<sup>2</sup>
GenFlex ISO Insulation

Minimum 2" thick 1 or 2 with 3  $1:1.78 \text{ ft}^2$ 

Note: Base layer shall be fastened with fasteners and density described. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Top Insulation Layer	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
SECUROCK Gypsum Fiber Roof Board		
Minimum ¼" thick	N/A	N/A

Note: Top layer shall be adhered to top insulation with I.S.O. Stick applied in continuous 3/4" to 1" wide ribbons spaced 6" o.c. or I.S.O. Spray R applied in 3/4" to 1" wide ribbons spaced 12" o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

**Membrane:** Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

**Maximum Design** 

**Pressure:** -67.5 psf. (See General Limitation #7)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24

Page 7 of 40

Deck Type 2I: Steel, Insulated

**Deck Description:** Minimum 22 ga., Grade 33, Type B steel decking attached to steel supports

spaced 6 ft o.c. with 5/8" diameter puddle welds 6" o.c. and with side laps attached using  $\frac{1}{4}$ " - 14 x  $\frac{7}{8}$ " HWH self-drilling fasteners spaced 24" o.c.

This Tested Assembly has been analyzed for allowable deck stress. See

**Evidence Submitted Table.** 

System Type B(4): Base layer of insulation mechanically fastened, top layer adhered: membrane

self-adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
GenFlex ISO Insulation Minimum 2" thick	1 or 2 with 3	1:1.78 ft <sup>2</sup>
Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
GenFlex HD ISO Minimum ½" thick	N/A	N/A

Note: Base layer shall be mechanically attached with fasteners and density described. All other layers of insulation shall be adhered to base insulations with I.S.O. Twin Pack Insulation Adhesive in continuous ½" to ¾" wide ribbons spaced 6" o.c. or I.S.O. Spray R, or I.S.O. Stick applied in continuous ¾" to 1" wide ribbons spaced 6" o.c. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

**Membrane:** Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

**Maximum Design** 

**Pressure:** -67.5 psf. (See General Limitation #7)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 8 of 40

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga. Grade 33 steel deck is secured to supports spaced 6 ft. o.c.

with Traxx/5 fasteners spaced 6" o.c. at the supports (two fasteners installed at each bearing attachment point) and Traxx/1 fasteners 12" o.c. at the side laps.

This Tested Assembly has been analyzed for allowable deck stress. See

**Evidence Submitted Table.** 

**System Type B(5):** Base layer of insulation mechanically fastened, top layer adhered: membrane

self-adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
GenFlex ISO Insulation Minimum 2" thick	1 or 2 with 3	1:1 ft <sup>2</sup>
<b>Top Insulation Layer</b>	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
GenFlex HD ISO Minimum ½" thick	N/A	N/A

Note: Base layer shall be mechanically attached with fasteners and density described. Top layer of insulation shall be adhered to base insulations with I.S.O. Twin Pack Insulation Adhesive in continuous ½" to ¾" wide beads spaced 12" o.c. or I.S.O. Stick applied in continuous ¾" to 1" wide ribbons spaced 12" o.c. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

**Membrane:** Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

**Maximum Design** 

**Pressure:** -90 psf. (See General Limitation #7)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 9 of 40

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga. Grade 33, Type B steel deck is secured to supports spaced 6 ft.

o.c. with Traxx/5 fasteners spaced 6" o.c. at the supports (two fasteners installed at each bearing attachment point) and Traxx/1 fasteners 12" o.c. at the side laps.

This Tested Assembly has been analyzed for allowable deck stress. See

**Evidence Submitted Table.** 

**System Type B(6):** Base layer of insulation mechanically fastened, top layer adhered: membrane

self-adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners	Fastener
	(Table 3)	Density/ft <sup>2</sup>
<b>GenFlex ISO Insulation</b>		
Minimum 2" thick	1 or 2 with 3	1:1 ft <sup>2</sup>

Note: Base layer shall be fastened with fasteners and density described. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

<b>Top Insulation Layer</b>	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
<b>GenFlex ISO Insulation</b>	( ,	,
Minimum 1" thick	N/A	N/A

Note: Top layer shall be adhered to base insulation with I.S.O. Twin Pack Insulation Adhesive in continuous ½" to ¾" wide beads spaced 4" o.c., I.S.O. Stick applied in continuous ¾" to 1" wide ribbons spaced 4" o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

**Maximum Design** 

**Pressure:** -90 psf. (See General Limitation #7)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 10 of 40

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga. Grade 80 steel deck is secured to supports spaced 6 ft. o.c.

with Traxx/5 fasteners spaced 6" o.c. at the supports (two fasteners installed at each bearing attachment point) and Traxx/1 fasteners 24" o.c. at the side laps.

This Tested Assembly has been analyzed for allowable deck stress. See

**Evidence Submitted Table.** 

System Type B(7): Base layer of insulation mechanically fastened, top layer adhered: membrane

self-adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer (Optional) Insulation Fasteners Fastener Density/ft<sup>2</sup>

(Table 3)

**GenFlex ISO Insulation** 

Minimum 1" thick N/A N/A

Middle Insulation Layer Insulation Fasteners Fastener Density/ft<sup>2</sup>

(Table 3)

**GenFlex ISO Insulation** 

Minimum 2" thick 1 or 2 with 3 1:1 ft<sup>2</sup>

Note: Base layer shall be loose laid. Middle layer shall be simultaneously fastened with fasteners and density described. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Top Insulation Layer Insulation Fasteners Fastener Density/ft<sup>2</sup>
(Table 3)

GenFlex HD ISO (Table

Minimum ½" thick N/A N/A

Note: Top layer shall be adhered to top insulation with I.S.O. Twin Pack Insulation Adhesive in continuous ½" to ¾" wide ribbons spaced 4" o.c. or, I.S.O. Stick applied in continuous ¾" to 1" wide ribbons spaced 4" o.c. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Membrane: Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

**Maximum Design** 

**Pressure:** -90 psf. (See General Limitation #7)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 11 of 40

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga. Grade 33, Type B steel deck is secured to supports spaced 6

ft. o.c. with Traxx/5 fasteners spaced 6" o.c. at the supports (one fastener installed at each bearing attachment point) and Traxx/1 fasteners 24" o.c. at the

side laps.

This Tested Assembly has been analyzed for allowable deck stress. See

**Evidence Submitted Table.** 

**System Type C(1):** Membrane self-adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
<b>GenFlex ISO Insulation</b>	,	v
Minimum 1.5" thick	N/A	N/A
Top Insulation Layer	Insulation Fasteners	Fastener
GenFlex HD ISO, GenFlex ISO Insulation	(Table 3)	Density/ft <sup>2</sup>
Minimum 1" thick	1 or 2 with 3	1: 1.8 ft <sup>2</sup>
DensDeck Prime, SECUROCK Gypsum-Fiber Boards		
Minimum ¼" thick	1 or 2 with 3	1: 1.8 ft <sup>2</sup>

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

**Membrane:** Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

**Maximum Design** 

**Pressure** -45 psf. (See General Limitation #7)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 12 of 40

**Deck Type 21:** Steel, Insulated **Deck Description:** 18 - 22 ga. 33 ksi

**System Type C(2):** Membrane self-adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer (Optional)	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
GenFlex ISO Insulation	, ,	·
Minimum ½" thick	N/A	N/A
Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
GenFlex ISO Insulation	,	v
Minimum 1.25" thick	1 or 2 with 3	1:2.7ft <sup>2</sup>
DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board		
Minimum ½" thick	1 or 2 with 3	$1:2.7 \text{ ft}^2$

Note: All layers shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

**Membrane:** Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

**Maximum Design** 

**Pressure:** -45 psf. (See General Limitation #9)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 13 of 40

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga., Grade 33, Type B steel decking attached to steel supports

spaced 6 ft o.c. with 5/8" diameter puddle welds 6" o.c. and with side laps

attached using ½" – 14 x 7/8" HWH self-drilling fasteners spaced 24" o.c.

This Tested Assembly has been analyzed for allowable deck stress. See

**Evidence Submitted Table.** 

**System Type C(3):** Membrane self-adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
GenFlex ISO Insulation Minimum 1" thick	N/A	N/A
Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
SECUROCK Gypsum-Fiber Roof Board Minimum ¼" thick	1 or 2 with 3	1:1.78 ft <sup>2</sup>
GenFlex ISO Insulation Minimum 1.5" thick	1 or 2 with 3	1:1.78 ft <sup>2</sup>
DensDeck Prime Minimum ½" thick	1 or 2 with 3	1:1.78 ft <sup>2</sup>

Note: All layers shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

Membrane: Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

**Maximum Design** 

**Pressure:** -45 psf. (See General Limitation #7)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 14 of 40

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga., Grade 33, Type B steel decking attached to steel supports

spaced 6 ft o.c. with 5/8" diameter puddle welds 6" o.c. and with side laps

attached using  $\frac{1}{4}$ " – 14 x 7/8" HWH self-drilling fasteners spaced 24" o.c.

This Tested Assembly has been analyzed for allowable deck stress. See

**Evidence Submitted Table.** 

**System Type C(4):** Membrane self-adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
<b>GenFlex ISO Insulation</b>		
Minimum 1.5" thick	N/A	N/A
Top Insulation Layer	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
GenFlex ISO Insulation	` ,	·
Minimum 2" thick	1 or 2 with 3	1:2.67 ft <sup>2</sup>
DensDeck Prime, SECUROCK Gypsum-Fiber Roof	Board	
Minimum ½" thick	1 or 2 with 3	$1:2.67 \text{ ft}^2$

Note: All layers shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

**Membrane** Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

**Maximum Design** 

**Pressure:** -45 psf. (See General Limitation #7)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 15 of 40

**Deck Type 21:** Steel, Insulated **Deck Description:** 18 - 22 ga. 33 ksi

**System Type C(5):** Membrane self-adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
<b>GenFlex ISO Insulation</b>	,	•
Minimum 1.5" thick	N/A	N/A
Top Insulation Layer	<b>Insulation Fasteners</b>	Fastener
•	(Table 3)	Density/ft <sup>2</sup>
DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board	,	·
Minimum <sup>1</sup> / <sub>4</sub> " thick	1 or 2 with 3	$1:2.7 \text{ ft}^2$
GenFlex ISO Insulation		
Minimum 1.5" thick	1 or 2 with 3	$1:2.7 \text{ ft}^2$

Note: All layers shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

Membrane: Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

**Maximum Design** 

**Pressure:** -45 psf. (See General Limitation #9)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 16 of 40

**Deck Type 2I:** Steel, Insulated **Deck Description:** 18 - 22 ga. 33 ksi

**System Type C(6):** Membrane self-adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Insulation Layer	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
DensDeck Prime, SECUROCK Gypsum-Fiber Roof Board	·	•
Minimum <sup>1</sup> / <sub>4</sub> " thick	1 or 2 with 3	$1:2.7 \text{ ft}^2$
GenFlex ISO Insulation		
Minimum 1.5" thick	1 or 2 with 3	$1:2.7 \text{ ft}^2$

Note: All layers shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

**Membrane:** Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

**Maximum Design** 

**Pressure:** -45 psf. (See General Limitation #9)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 17 of 40

**Deck Type 2I:** Steel, Insulated **Deck Description:** 18 - 22 ga. 33 ksi

**System Type C(7):** Membrane self-adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

(Optional) Vapor Retarder Polyethylene Sheet 4-6 mil thick Min. 2" wide laps sealed with duct tape

One or more layers of any of the following insulations.

Base Insulation Layer Insulation Fasteners (Table 3) Fastener Density/ft²

GenFlex ISO Insulation, Tapered GenFlex ISO Insulation

Minimum 1.5" thick N/A N/A

Top Insulation Layer Insulation Fasteners Fastener (Table 3) Density/ft<sup>2</sup>

**SECUROCK Gypsum-Fiber Roof Board** 

Minimum ½" thick 1 or 2 with 3 1:4 ft<sup>2</sup>

Note: All layers shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

**Membrane:** Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

**Maximum Design** 

**Pressure:** -45 psf. (See General Limitation #9)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 18 of 40

**Deck Type 2I:** Steel, Insulated **Deck Description:** 18 - 22 ga. 33 ksi

**System Type C(8):** Membrane fully adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
GenFlex ISO Insulation	,	•
Minimum 1.5" thick	N/A	N/A
Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
GenFlex HD ISO	,	•
Minimum ½" thick	1 or 2 with 3	1:2.7ft <sup>2</sup>
GenFlex ISO Insulation		
Minimum 1" thick	1 or 2 with 3	1:2.7ft <sup>2</sup>
DensDeck Prime, SECUROCK Gypsum Fiber Board		
Minimum 1/4"	1 or 2 with 3	1:2.7ft <sup>2</sup>

Note: All layers shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

Membrane: Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

**Maximum Design** 

**Pressure:** -45 psf. (See General Limitation #9)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 19 of 40

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga., Grade 33, Type B steel decking attached to steel supports

spaced 6 ft. o.c. with #12-24 x 1-1/4" HWH self-drilling fasteners spaced 6" o.c. and with side laps attached using  $\frac{1}{4}$ "-14 x 7/8" HWH self-drilling fasteners

spaced 24" o.c.

This Tested Assembly has been analyzed for allowable deck stress. See

**Evidence Submitted Table.** 

**System Type C(9):** Membrane self-adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer (Optional)	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
GenFlex ISO Insulation		
Minimum ½" thick	N/A	N/A
Top Insulation Layer	Insulation Fasteners	Fastener
Top Insulation Enjor	(Table 3)	Density/ft <sup>2</sup>
GenFlex ISO Insulation		
Minimum 1.5" thick	1 or 2 with 3	1:1.6 ft <sup>2</sup>
SECUROCK Gypsum Fiber Roof Board, DensDeck Prime		
Minimum ½" thick	1 or 2 with 3	1:1.6 ft <sup>2</sup>

Note: All layers shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

**Membrane:** Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

**Maximum Design** 

**Pressure:** -52.5 psf. (See General Limitation #7)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 20 of 40

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga., Grade 33, Type B Steel decking attached to Steel supports

spaced 6 ft. o.c. with #12-24 x 1-1/4" HWH self-drilling fasteners spaced 6" o.c. and with side laps attached using  $\frac{1}{4}$ "-14 x 7/8" HWH self-drilling fasteners

spaced 24" o.c.

This Tested Assembly has been analyzed for allowable deck stress. See

**Evidence Submitted Table.** 

**System Type C(10):** All layers of insulation simultaneously attached; membrane full adhered.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

**Vapor Barrier:** V-Force self-adhered to top of each deck rib with 3" wide side laps.

**Fire Barrier:** Minimum ¼" thick SECUROCK Gypsum-Fiber Roof Board loose laid over deck.

One or more layers of any of the following insulations.

Base Insulation Layer (Optional)	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
<b>GenFlex ISO Insulation</b>	, ,	·
Minimum 1" thick	N/A	N/A
<b>Top Insulation Layer</b>	Insulation Fasteners	Fastener
	(Table 3)	Density/ft <sup>2</sup>
GenFlex ISO Insulation		
Minimum 3" thick	1 or 2 with 3	$1:4.0 \text{ ft}^2$

Note: All layers shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

Membrane: Min. 45 mil. EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

Maximum Design

**Pressure:** -52.5 psf. (See General Limitation #7)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 21 of 40

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga., Grade 33, Type B steel decking attached to steel supports

spaced 6 ft o.c. with 5/8" diameter puddle welds 6" o.c. and with side laps

attached using  $\frac{1}{4}$ " – 14 x 7/8" HWH self-drilling fasteners spaced 24" o.c.

This Tested Assembly has been analyzed for allowable deck stress. See

**Evidence Submitted Table.** 

**System Type C(11):** Membrane fully adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
GenFlex ISO Insulation Minimum ½"thick	N/A	N/A
Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
DensDeck Prime, SECUROCK Gypsum Fiber Roof Board Minimum ½" thick	1 or 2 with 3	1:1.78 ft <sup>2</sup>

Note: All layers shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

Membrane: Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

**Maximum Design** 

**Pressure:** -52.5 psf. (See General Limitation #7)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 22 of 40

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga. Grade 33, Type B steel deck is secured to supports spaced 6 ft.

o.c. with Traxx/5 fasteners spaced 6" o.c. at the supports (one fastener Installed at each bearing attachment point) and Traxx/1 fasteners 24" o.c. at the side laps

This Tested Assembly has been analyzed for allowable deck stress. See

**Evidence Submitted Table.** 

**System Type C(12):** Membrane fully adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
GenFlex ISO Insulation		
Minimum 1.5" thick	N/A	N/A
Top Insulation Layer	<b>Insulation Fasteners</b>	Fastener
•	(Table 3)	Density/ft <sup>2</sup>
GenFlex HD ISO	,	•
Minimum ½" thick	1 or 2 with 3	1: 1.33 ft <sup>2</sup>
GenFlex ISO Insulation		
Minimum 1" thick	1 or 2 with 3	1: 1.33 ft <sup>2</sup>
DensDeck Prime, SECUROCK Gypsum -Fiber Roof Boa	ırd	
Minimum 1/4 <sup>1</sup> / <sub>4</sub> " thick	1 or 2 with 3	1: 1.33 ft <sup>2</sup>

Note: All layers shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

**Membrane:** Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

**Maximum Design** 

**Pressure:** -60 psf. (See General Limitation #7)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 23 of 40

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga., Grade 33, Type B steel decking attached to steel supports

spaced 6 ft. o.c. with #12-24 x 1-1/4" HWH self-drilling fasteners spaced 6" o.c. and with side laps attached using  $\frac{1}{4}$ "-14 x 7/8" HWH self-drilling fasteners

spaced 24" o.c.

This Tested Assembly has been analyzed for allowable deck stress. See

**Evidence Submitted Table.** 

**System Type C(13):** Membrane fully adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
GenFlex ISO Insulation		
Minimum ½" thick	N/A	N/A
<b>Top Insulation Layer</b>	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
SECUROCK Gypsum-Fiber Roof Board	,	·
Minimum ½" thick	1 or 2 with 3	1:1.78 ft <sup>2</sup>

Note: All layers shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

Membrane: Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

**Maximum Design** 

**Pressure:** -60 psf. (See General Limitation #7)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 24 of 40

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga., Grade 33, Type B steel decking attached to steel supports

spaced 6 ft o.c. with 5/8" diameter puddle welds 6" o.c. and with side laps attached using  $\frac{1}{4}$ " - 14 x  $\frac{7}{8}$ " HWH self-drilling fasteners with  $\frac{1}{2}$ " washers

spaced 12" o.c.

This Tested Assembly has been analyzed for allowable deck stress. See

**Evidence Submitted Table.** 

**System Type C(14):** Membrane self-adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

<b>Base Insulation Layer (Optional)</b>	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
<b>GenFlex ISO Insulation</b>	,	·
Minimum 1/2" thick	N/A	N/A
Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
<b>GenFlex ISO Insulation</b>	,	v
Minimum 1.5" thick	1 or 2 with 3	$1:1.78 \text{ ft}^2$
DensDeck Prime, SECUROCK Gypsum Fibe	er Roof Board	
Minimum ½" thick	1 or 2 with 3	1:1.78 ft <sup>2</sup>

Note: All layers shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

**Membrane:** Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

**Maximum Design** 

**Pressure:** -60 psf. (See General Limitation #7)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 25 of 40

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga. Grade 33, Type B steel deck is secured to supports spaced 6 ft.

o.c. with Traxx/5 fasteners spaced 6" o.c. at the supports (one fastener installed at each bearing attachment point) and Traxx/1 fasteners 24" o.c. at the side laps.

This Tested Assembly has been analyzed for allowable deck stress. See

**Evidence Submitted Table.** 

**System Type C(15):** Membrane self-adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer	Insulation Fasteners	Fastener
·	(Table 3)	Density/ft <sup>2</sup>
<b>GenFlex ISO Insulation</b>		•
Minimum 1.5" thick	N/A	N/A

Note: All layers shall be simultaneously fastened; see top layer below for fasteners and density. Insulation panels listed are minimum sizes and dimensions; if larger panels are used, the number of fasteners shall be increased maintaining the same fastener density. Please refer to Roofing Application Standard RAS 117 for insulation attachment.

Top Insulation Layer	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
GenFlex HD ISO		
Minimum ½" thick	1 or 2 with 3	1:1.33 ft <sup>2</sup>
DensDeck Prime, SECUROCK Gypsum Fiber Roof Boa	ırd	
Minimum 1/4" thick	1 or 2 with 3	1:1.33 ft <sup>2</sup>
<b>GenFlex ISO Insulation</b>		
Minimum 1" thick	1 or 2 with 3	1:1.33 ft <sup>2</sup>

Membrane: Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

**Maximum Design** 

**Pressure:** -60 psf. (See General Limitation #7)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 26 of 40

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga., Grade 33, Type B steel decking attached to steel supports

spaced 6 ft o.c. with 5/8" diameter puddle welds 6" o.c. and with side laps attached using  $\frac{1}{4}$ " - 14 x  $\frac{7}{8}$ " HWH self-drilling fasteners spaced 24" o.c.

This Tested Assembly has been analyzed for allowable deck stress. See

**Evidence Submitted Table.** 

**System Type C(16):** Membrane self-adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners	Fastener
	(Table 3)	Density/ft <sup>2</sup>

**GenFlex ISO Insulation** 

Minimum ½" thick N/A N/A

Top Insulation Layer	Insulation Fasteners	Fastener
	(Table 3)	Density/ft <sup>2</sup>

SECUROCK Gypsum-Fiber Roof Board

Minimum  $\frac{1}{2}$ " thick 1 or 2 with 3 1:2.13 ft<sup>2</sup>

Note: All layers shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

Membrane: Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

**Maximum Design** 

**Pressure:** -60 psf. (See General Limitation #7)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 27 of 40

**Deck Type 2I:** Steel, Insulated

**Deck Description:** 18 - 22 ga. 33 ksi

**System Type C(17):** Membrane fully adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
GenFlex ISO Insulation	` ,	v
Minimum 1" thick	N/A	N/A
DensDeck Prime, SECUROCK Gypsum Fiber	· Roof Board	
Minimum <sup>1</sup> / <sub>4</sub> " thick	N/A	N/A
Top Insulation Layer	Insulation Fasteners	Fastener
	(Table 3)	Density/ft <sup>2</sup>
SECUROCK Gypsum-Fiber Roof Board	` ,	•
Minimum 1/2" thick	1 or 2 with 3	$1:4.0 \text{ ft}^2$

Note: All layers shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

**Membrane:** Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld at

the 2" wide side laps.

**Maximum Design** 

**Pressure:** -62.5 psf. (See General Limitation #9)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 28 of 40

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga., Grade 33, Type B steel decking attached to steel supports

spaced 6 ft o.c. with 5/8" diameter puddle welds 6" o.c. and with side laps attached using  $\frac{1}{4}$ " -  $14 \times \frac{7}{8}$ " HWH self-drilling fasteners spaced 24" o.c.

This Tested Assembly has been analyzed for allowable deck stress. See

**Evidence Submitted Table.** 

**System Type C(18):** Membrane self-adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer (Optional)	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
<b>GenFlex ISO Insulation</b>	,	·
Minimum 1/2" thick	N/A	N/A
Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
SECUROCK Gypsum-Fiber Roof Board	,	·
Minimum ¼" thick	1 or 2 with 3	1:1.6 ft <sup>2</sup>
GenFlex ISO Insulation		
Minimum 1-1/2" thick	1 or 2 with 3	1:1.6 ft <sup>2</sup>
DensDeck Prime		
Minimum ½" thick	1 or 2 with 3	1:1.6 ft <sup>2</sup>

Note: All layers shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

Membrane: Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

**Maximum Design** 

**Pressure:** -67.5 psf. (See General Limitation #7)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 29 of 40

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga. Grade 33, Type B steel deck is secured to supports spaced 6

ft. o.c. with Traxx/5 fasteners spaced 6" o.c. at the supports (two fasteners installed at each bearing attachment point) and Traxx/1 fasteners 12" o.c. at the

side laps.

This Tested Assembly has been analyzed for allowable deck stress. See

**Evidence Submitted Table.** 

**System Type C(19):** Membrane self-adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
GenFlex ISO Insulation		
Minimum 1.5" thick	N/A	N/A
Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
DensDeck Prime, SECUROCK Gypsum Fiber Roof Board	,	·
Minimum ½" thick	1 or 2 with 3	1:1.33 ft <sup>2</sup>

Note: All layers shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

Membrane: Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

**Maximum Design** 

**Pressure:** -75 psf. (See General Limitation #7)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 30 of 40

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga. Grade 33, Type B steel deck is secured to supports spaced 6 ft.

o.c. with Traxx/5 fasteners spaced 6" o.c. at the supports (one fastener installed at each bearing attachment point) and Traxx/1 fasteners 24" o.c. at the side laps.

This Tested Assembly has been analyzed for allowable deck stress. See

**Evidence Submitted Table.** 

System Type C(20): Membrane fully adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer (Optional)	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
DensDeck Prime, GenFlex HD ISO	,	·
Minimum ½" thick	N/A	N/A
Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
GenFlex ISO Insulation,	,	·
Minimum 2" thick	1 or 2 with 3	1:1.6 ft <sup>2</sup>
DensDeck Prime, SECUROCK Gypsum Fiber Roof Board		
Minimum ½" thick	1 or 2 with 3	1:1.6 ft <sup>2</sup>

Note: All layers shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

Membrane: Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

**Maximum Design** 

**Pressure:** -75 psf. (See General Limitation #7)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 31 of 40

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga. Grade 33, Type B steel deck is secured to supports spaced 6 ft.

o.c. with Traxx/5 fasteners spaced 6" o.c. at the supports (one fastener installed at each bearing attachment point) and Traxx/1 fasteners 24" o.c. at the side laps.

This Tested Assembly has been analyzed for allowable deck stress. See

**Evidence Submitted Table.** 

**System Type C(21):** Membrane self-adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Insulation Layer	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
GenFlex ISO Insulation		
Minimum 2" thick	1 or 2 with 3	$1:1.6 \text{ ft}^2$
DensDeck Prime, SECUROCK Gypsum Fiber Roof Boa	ırd	
Minimum ½" thick	1 or 2 with 3	1:1.6 ft <sup>2</sup>

Note: All layers shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

Membrane: Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

**Maximum Design** 

**Pressure:** -75 psf. (See General Limitation #7)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 32 of 40

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga., Grade 33, Type B steel decking attached to steel supports

spaced 6 ft o.c. with 5/8" diameter puddle welds 6" o.c. and with side laps attached using  $\frac{1}{4}$ " - 14 x  $\frac{7}{8}$ " HWH self-drilling fasteners spaced 24" o.c.

This Tested Assembly has been analyzed for allowable deck stress. See

**Evidence Submitted Table.** 

System Type C(22): Membrane self-adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
GenFlex ISO Insulation	,	v
Minimum 1/2" thick	N/A	N/A
Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
SECUROCK Gypsum Fiber Roof Board Minimum ½" thick	1 or 2 with 3	1:1.78 ft <sup>2</sup>

Note: All layers shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

Membrane: Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

**Maximum Design** 

**Pressure:** -82.5 psf. (See General Limitation #7)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 33 of 40

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga., Grade 33, Type B steel deck is secured to supports spaced 6 ft.

o.c. with Traxx/5 fasteners spaced 6" o.c. at the supports (one fastener installed at each bearing attachment point) and Traxx/1 fasteners 24" o.c. at the side laps.

This Tested Assembly has been analyzed for allowable deck stress. See

**Evidence Submitted Table.** 

System Type C(23): Membrane fully adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations.

Base Insulation Layer (Optional)	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
<b>GenFlex ISO Insulation</b>	,	•
Minimum ½" thick	N/A	N/A
Top Insulation Layer	Insulation Fasteners	Fastener Density/ft <sup>2</sup>
GenFlex ISO Insulation	(Table 3)	Density/it
Minimum 1 ½" thick	1 or 2 with 3	1:1.33 ft <sup>2</sup>
DensDeck Prime, SECUROCK Gypsum Fiber Roof Board		
Minimum 1/2" thick	1 or 2 with 3	1:1.33 ft <sup>2</sup>

Note: All layers shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

**Membrane:** Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

**Maximum Design** 

**Pressure:** -90 psf. (See General Limitation #7)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 34 of 40

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga. Grade 33, Type B steel deck is secured to supports spaced 6 ft.

o.c. with Traxx/5 fasteners spaced 6" o.c. at the supports (one fastener installed at each bearing attachment point) and Traxx/1 fasteners 24" o.c. at the side laps.

This Tested Assembly has been analyzed for allowable deck stress. See

**Evidence Submitted Table.** 

**System Type C(24):** Membrane self-adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Insulation Layer	<b>Insulation Fasteners</b>	Fastener
•	(Table 3)	Density/ft <sup>2</sup>
SECUROCK Gypsum Fiber Roof Board		
Minimum ½" thick	1 or 2 with 3	1:1.33 ft <sup>2</sup>

Note: All layers shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

**Membrane:** Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

**Maximum Design** 

**Pressure:** -90 psf. (See General Limitation #7)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 35 of 40

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga. Grade 33 steel deck is secured to supports spaced 6 ft. o.c.

with Traxx/5 fasteners spaced 6" o.c. at the supports (two fasteners installed at each bearing attachment point) and Traxx/1 fasteners 24" o.c. at the side laps.

This Tested Assembly has been analyzed for allowable deck stress. See

**Evidence Submitted Table.** 

**System Type C(25):** Membrane self-adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
GenFlex ISO Insulation Minimum 1/2" thick	N/A	N/A
GenFlex ISO Insulation	(=======)	
Minimum 2" thick	1 or 2 with 3	1:1 ft <sup>2</sup>
DensDeck Prime, SECUROCK Gypsum Fibe	er Roof Board	
Minimum ½" thick	1 or 2 with 3	1:1ft <sup>2</sup>

Note: All layers shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

Membrane: Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

**Maximum Design** 

**Pressure:** -90 psf. (See General Limitation #7)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 36 of 40

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga. Grade 33, Type B steel deck is secured to supports spaced 6 ft.

o.c. with Traxx/5 fasteners spaced 6" o.c. at the supports (two fasteners installed at each bearing attachment point) and Traxx/1 fasteners 24" o.c. at the side laps.

This Tested Assembly has been analyzed for allowable deck stress. See

**Evidence Submitted Table.** 

**System Type C(26):** Membrane self-adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

<b>Base Insulation Layer (Optional)</b>	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
GenFlex ISO Insulation	, ,	•
Minimum 1/2" thick	N/A	N/A
Top Insulation Layer	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
SECUROCK Gypsum Fiber Roof Board, DensI	Deck Prime	
Minimum ½" thick	1 or 2 with 3	1:1 ft <sup>2</sup>

Note: All layers shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

**Membrane:** Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

**Maximum Design** 

**Pressure:** -90 psf. (See General Limitation #7)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 37 of 40

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga. Grade 80 steel deck is secured to supports spaced 6 ft. o.c. with

Traxx/5 fasteners spaced 6" o.c. at the supports (two fasteners installed at each bearing attachment point) and Traxx/1 fasteners 24" o.c. at the side laps.

This Tested Assembly has been analyzed for allowable deck stress. See

**Evidence Submitted Table.** 

**System Type C(27):** Membrane self-adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

<b>Base Insulation Layer (Optional)</b>	Insulation Fasteners (Table 3)	Fastener Density/ft²
<b>GenFlex ISO Insulation</b>	,	•
Minimum 1/2" thick	N/A	N/A
Top Insulation Layer	Insulation Fasteners (Table 3)	Fastener Density/ft <sup>2</sup>
<b>GenFlex ISO Insulation</b>	,	v
Minimum 2" thick	1 or 2 with 3	1:1 ft <sup>2</sup>
SECUROCK Gypsum Fiber Roof Board, De	nsDeck Prime	
Minimum ½" thick	1 or 2 with 3	1:1 ft <sup>2</sup>

Note: All layers shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

**Membrane:** Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

**Maximum Design** 

**Pressure:** -90 psf. (See General Limitation #7)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 38 of 40

**Deck Type 2I:** Steel, Insulated

**Deck Description:** Minimum 22 ga. Grade 80 steel deck is secured to supports spaced 6 ft.

o.c. with Traxx/5 fasteners spaced 6" o.c. at the supports (two fasteners installed at each bearing attachment point) and Traxx/1 fasteners 24" o.c. at the side laps.

This Tested Assembly has been analyzed for allowable deck stress. See

**Evidence Submitted Table.** 

System Type C(28): Membrane self-adhered over mechanically fastened insulation.

All General and System Limitations apply. Roof accessories not listed in Table 1 of this NOA are not approved and shall not be installed unless said accessories demonstrate compliance with prescriptive Florida Building Code requirements and are field fabricated utilizing the approved membranes listed in Table 1.

One or more layers of any of the following insulations:

Base Insulation Layer (Optional)	Insulation Fasteners (Table 3)	Fastener Density/ft²
GenFlex ISO Insulation		
Minimum 1/2" thick	N/A	N/A
Top Insulation Layer	<b>Insulation Fasteners</b>	Fastener
	(Table 3)	Density/ft <sup>2</sup>
SECUROCK Gypsum Fiber Roof Board, DensDe	eck Prime	
Minimum ½" thick	1 or 2 with 3	1:1 ft <sup>2</sup>

Note: All layers shall be mechanically attached with fasteners and density described above. Insulation panels listed are minimum sizes and dimensions; if larger panels are used the number of fasteners per board shall be increased maintaining the same fastener density. See Roofing Application Standard RAS 117 for fastening details.

Membrane: Min. 45 mil EZ TPO Peel and Stick HW self-adhered with 1.5" wide heat weld

at the 2" wide side laps.

**Maximum Design** 

**Pressure:** -90 psf. (See General Limitation #7)



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 39 of 40

#### STEEL DECK SYSTEM LIMITATIONS:

- 1. If mechanical attachment to the structural deck through the lightweight insulating concrete is proposed, a field withdrawal resistance testing shall be performed to determine equivalent or enhanced fastener patterns and density. All testing and fastening design shall be in compliance with Testing Application Standard TAS 105 and Roofing Application Standard RAS 117 and/or RAS 137, calculations shall be signed and sealed by a Florida registered Professional Engineer, Registered Architect, or Registered Roof Consultant.
- 2. For steel deck application where specific deck construction is not referenced: The deck shall be a minimum 22 gage attached with 5/8" puddle welds with weld washers at every flute with maximum deck spans of 5 ft. o.c.

#### **GENERAL LIMITATIONS:**

- 1. Fire classification is not part of this acceptance; refer to a current Approved Roofing Materials Directory for fire ratings of this product.
- 2. Insulation may be installed in multiple layers. The first layer shall be attached in compliance with Product Control Approval guidelines. All other layers shall be adhered in a full mopping of approved asphalt applied within the EVT range and at a rate of 20-40 lbs./sq., or mechanically attached using the fastening pattern of the top layer
- 3. All standard panel sizes are acceptable for mechanical attachment. When applied in approved asphalt, panel size shall be 4' x 4' maximum.
- 4. An overlay and/or recovery board insulation panel is required on all applications over closed cell foam insulations when the base sheet is fully mopped. If no recovery board is used the base sheet shall be applied using spot mopping with approved asphalt, 12" diameter circles, 24" o.c.; or strip mopped 8" ribbons in three rows, one at each side lap and one down the center of the sheet allowing a continuous area of ventilation. Encircling of the strips is not acceptable. A 6" break shall be placed every 12' in each ribbon to allow cross ventilation. Asphalt application of either system shall be at a minimum rate of 12 lbs./sq.

### Note: Spot attached systems shall be limited to a maximum design pressure of -45 psf.

- 5. Fastener spacing for insulation attachment is based on a Minimum Characteristic Force (F') value of 275 lbf., as tested in compliance with Testing Application Standard TAS 105. If the fastener value, as field-tested, are below 275 lbf. insulation attachment shall not be acceptable.
- 6. Fastener spacing for mechanical attachment of anchor/base sheet or membrane attachment is based on a minimum fastener resistance value in conjunction with the maximum design value listed within a specific system. Should the fastener resistance be less than that required, as determined by the Building Official, a revised fastener spacing, prepared, signed and sealed by a Florida registered Professional Engineer, Registered Architect, or Registered Roof Consultant may be submitted. Said revised fastener spacing shall utilize the withdrawal resistance value taken from Testing Application Standards TAS 105 and calculations in compliance with Roofing Application Standard RAS 117
- 7. Perimeter and corner areas shall comply with the enhanced uplift pressure requirements of these areas. Fastener densities shall be increased for both insulation and base sheet as calculated in compliance with Roofing Application Standard RAS 117. Calculations prepared, signed and sealed by a Florida registered Professional Engineer, Registered Architect, or Registered Roof Consultant (When this limitation is specifically referred within this NOA, General Limitation #9 will not be applicable.)
- 8. All attachment and sizing of perimeter nailers, metal profile, and/or flashing termination designs shall conform to Roofing Application Standard RAS 111 and applicable wind load requirements.
- 9. The maximum designed pressure limitation listed shall be applicable to all roof pressure zones (i.e. field, perimeters, and corners). Neither rational analysis, nor extrapolation shall be permitted for enhanced fastening at enhanced pressure zones (i.e. perimeters, extended corners and corners). (When this limitation is specifically referred within this NOA, General Limitation #7 will not be applicable.)
- 10. All products listed herein shall have a quality assurance audit in accordance with the Florida Building Code and Rule 61G20-3 of the Florida Administrative Code.

#### END OF THIS ACCEPTANCE



NOA No.: 24-0418.04 Expiration Date: 08/29/25 Approval Date: 08/29/24 Page 40 of 40